

**HUGH A. WYCKOFF WATER TREATMENT PLANT
PIPE STORAGE YARD RELOCATION
CONTRACTOR QUESTIONS AND ANSWERS
JULY 28, 2010**

1. Who is to obtain Land Disturbance Permit and who is to obtain Grading Permit?

The Owner has obtained the Land Disturbance Permit (Permit # 100134, dated July 19, 2010). The Grading Permit is issued after all erosion and sediment control devices are installed according to the approved plans. Therefore, the Contractor is responsible for obtaining the Grading Permit. For more information, please call the Site Inspections Section of the Development & Inspections Division at 770-528-2134.

2. Can a copy of the pre-bid sign in sheet be furnished to us ASAP?

The pre-bid sign in sheet is available at:

<http://www.cecincga.com/bid-information.html>

3. Can the grindings from the clearing stay on site?

No. All vegetative debris must be removed from site.

4. We just wanted to confirm that the pad elevations shown on the drawing are final grade that includes the GAB.

That is correct.

5. Sheet 5 states that Drop Inlet #1 is 'with weir-weir on two sides'. Please provide detailed design drawings of this configuration for bidding and future production purposes.

See detail on Sheet 8 of 16.

6. Is the contractor to include testing in their bid, or will the overall testing be handled under the separate testing & inspections RFP for the plant expansion?

Yes. Include testing in your bid. See Section 312000 – Earthmoving, 1.04. There is a Cash Allowance for Testing as ordered by Engineer. See Specification Section 012000, 1.05D.

This project is entirely separate from the plant expansion currently underway.

7. Can we chip the clearing debris and use the chips around the perimeter in front of the silt fence for additional erosion control OR should we plan on hauling off chips?

Both. You may use the chips in front of the silt fence for additional erosion control, but they will have to be removed at the end of the job. They will prevent/negatively affect the permanent grassing.